SPECIFICATIONS FOR WORK

TECHNICAL PROVISIONS

Incorporation of Montana Public Works Technical Specifications.

The Technical Specifications as found in Montana Public Works Standard Specifications (MPWSS), Sixth Edition, April 2010 Addendum; are hereby incorporated by reference and made a part of this Contract:

Incorporation of Montana Fish, Wildlife & Parks Technical Specifications and Modifications to MPW Technical Specifications.

In addition to the MPWSS Technical Specifications are the following Montana Fish, Wildlife & Parks Technical Specifications (modifications to MPWSS Technical Specifications).

SECTION 01010 - Summary of Work SECTION 01050 - Field Engineering

SECTION 01450 - Mobilization/Demobilization

SECTION 02910 - Revegetation

SECTION 014121 - Historical Site Work

SUMMARY OF WORK

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

PART 1 GENERAL

1.3 WORK SEQUENCE

Add the following:

- E. Substantial completion of the Fort Owen Parking Area must be achieved by June 1st, 2021.
- F. Other outside contractors may be completing paving work on Fort Owen Ranch Road at the same time as this project. CONTRACTOR shall coordinate work with other contractors as necessary.

FIELD ENGINEERING

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

PART 3 EXECUTION

1.1 CONSTRUCTION SURVEY

- A. Engineer will provide survey control (northing/easting) and benchmarks (local datum) for all designed alignments and profiles, as shown on the project drawings.
- B. Contractor will be responsible for setting slope stakes and grade stakes at 50' intervals on tangent sections and at 25' on horizontal curves, based on Owner provided control and alignment staking. The contractor will be responsible to provide own blue top staking prior to paving or gravel surfacing. Limit grade stake tolerances to +/-0.04'.

PART 4 MEASUREMENT AND PAYMENT

Add the following:

A. Contractor construction surveying will not be measured for payment and is considered incidental to other bid items in this contract.

MOBILIZATION/DEMOBILIZATION

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

- A. This item shall consist of the prepatory work and operations necessary performed by the Contractor for the movement of personnel, equipment, supplies, and incidentals to and from the work site. The work includes those actions necessary for obtaining necessary permits required for mobilization; for the establishment of all offices and facilities necessary to work on the project; for premiums on contract bonds; for insurance for the contract; and for other work on the various items on the project site. Mobilization costs for subcontracted work shall be considered to be included.
- B. Contractor's cost for administration, bonding, insurance, and site documents shall be included in mobilization and shall not be paid as a separate item.
- C. All equipment moved to the project sites shall be in good mechanical condition and free of fuel, oil, lubrication, or other fuel leaks. The Contractor shall immediately remove any equipment potentially or actually discharging environmentally damaging fluids.
- D. All equipment moved to the project sites shall be thoroughly cleaned before it is brought to the sites to prevent the introduction of weed seeds. Equipment removed fro the sites may not be returned to the sites again until it is thoroughly cleaned again.

PART 2 PRODUCTS – NOT USED

PART 3 EXECUTION – NOT USED

PART 4 MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

A. There will be no direct measurement of this item.

4.2 PAYMENT

B. Partial payments for mobilization/demobilization will be made based on the lump sum bid price as follows:

- ➤ 25% of the amount bid for mobilization/demobilization when the Contractor has moved on-site and begun construction activities.
- > 50% of the amount bid for mobilization/demobilization when 25% of the contract amount (exclusive mobilization/demobilization) has been completed.
- > 75% of the amount bid for mobilization/demobilization when 50% of the contract amount (exclusive mobilization/demobilization) has been completed.
- ➤ 100% of the amount bid for mobilization/demobilization when 75% of the contract amount (exclusive mobilization/demobilization) has been completed.

REVEGETATION

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

PART 1 GENERAL

1.1 DESCRIPTION

Add following:

This work also includes conserving, placing, and finishing topsoil placement at designated areas on the project drawings or as directed by the Engineer.

PART 2 PRODUCTS

2.1 SEED

Add the following:

Utilize the following seed mix for all areas to be seeded.

Seed Name	% Pure Live Seed	Lbs. Per Acre
Western Wheatgrass	30	*
Bluebunch Wheatgrass	20	*
Hard Fescue	20	*
Slender Wheatgrass	15	*
Smooth Bromegrass	15	*

^{*} Drilled Rate = 8 lbs/acre, Broadcast and Hydroseed Rate = 16 lbs/acre

2.2 TOPSOIL

Add the following:

Utilize all salvaged topsoil conserved from clearing and grubbing operations to cover excavation and embankment slopes prior to fertilizing, seeding, or mulching.

2.4 FERTILIZER

Add the following:

When broadcast seeding, apply the fertilizer separately. When drill seeding, do not apply seed and fertilizer in a single mixture. The fertilizer must be applied separately, either broadcast before seed application, or surface banded during seeding.

PART 4 MEASUREMENT AND PAYMENT

4.1 GENERAL

Delete this section and add the following:

- A. Revegetation will be measured and paid by the lump sum (LPSM) including all labor, equipment, materials and incidentals required for the completion of the work.
- B. Placing conserved topsoil will not be measured for payment and is considered incidental to other work items in this Contract.

SECTION 014121 - HISTORICAL SITE WORK

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Historical Site Preservation.

1.2 MATERIALS OWNERSHIP

- A. Unless otherwise indicated, demolition waste becomes property of Contractor.
- B. Historic items, relics, antiques, and other items of interest or value to Owner that may be uncovered during operations remain the property of Owner.

PART 2 - SITE AREAS

2.1 SITE AREA REQUIREMENTS

A. Refer to Division 01 – "Summary" for a description of the work and other site requirements.

PART 3 - EXECUTION

3.2 HISTORICAL SITE PRESERVATION

- A. Original Condition: The Contractor shall keep historical sites in original conditions or return to original conditions when applicable at Owners approval. This includes but is not limited to the following:
 - 1. Historical building(s) shall be kept in as is condition. Necessary construction in those buildings shall be done in a neat and workman like manner. Accumulated debris shall be cleaned each day to the condition the building was found in and to the satisfaction of the Park Management.
 - 2. It is expected that work in these buildings will be done with the utmost care. Any damage encountered shall be reported immediately to the Park Management to determine the method and means of repairs.
 - 3. Contractor is responsible for any damages to historical buildings, sidewalks, fences or any other items of archeological significance. All costs of Contractor caused damage shall be borne by the Contractor. Careless construction will not be tolerated and will be subject to a Stop Work order and evaluation of personnel and methods involved.
 - 4. Any disturbed ground shall be returned to original surface condition. Contractor is responsible for any seeding. Seeding mix will be specified by Owner.
 - 5. Contractor is responsible for bracing building rafters/walls to enable access and movement in buildings where building integrity is of concern. Contractor is responsible to bring any integrity issues of buildings to the Owner and Engineer.

- 6. Contractor is responsible for taking before and after pictures of all areas and buildings where work is done. The Contractor must provide the Owner with a digital copy of both before and after pictures when the job is completed.
- B. Uncovered Artifacts: For historical sites, there is a likely probability that artifacts will be uncovered during Work.
 - 1. If an artifact is uncovered, the Contractor is responsible to immediately notify the Park Management or onsite archaeologist.
 - 2. In the case of an uncovered artifact, the Contractor is expected to move ahead to another work area after notifying the proper personnel. Onsite archaeologist will need adequate time to carefully examine the artifact.
 - 3. It is at the archaeologist or Owner's discretion on when work can resume in the area of where the artifact was uncovered.
- C. Temporary Protection: Provide temporary barricades, signs and other protection required to prevent injury to people and damage to adjacent buildings and facilities.
 - 1. The Park will be closed to the public during construction. If necessary, Park management must be notified and updated on a routine basis as to scheduled closing and reopening of work areas. To the extent practical, Work shall be scheduled to minimize impact to the public (if Park is not closed during construction.)
 - 2. If necessary, provide protection to ensure safe passage of people around selective work area and to and from occupied portions of building.
 - 3. Protect walls, ceilings, floors, and other existing finish work that are to remain or that are exposed during selective operations.
- D. Temporary Shoring: Design, provide, and maintain shoring, bracing, and structural supports as required to preserve stability and prevent movement, settlement, or collapse of the building that is being worked on.
 - 1. The design for work in the buildings is, for the most practical degree, for an installation that would be possible with the least amount of hazard to the worker and the least likelihood of damage to the building. Historic buildings are fragile and contractors care is imperative.
- E. Remove temporary barricades and protections where hazards no longer exist.
- F. Remedy property damage: The Contractor shall promptly remedy damage and loss to property caused in whole or in part by the Contractor, a Subcontractor of any tier or level, or anyone employed by any of them, or by anyone for whose acts they may be liable and for which the Contractor is responsible.