



MONTANA FISH, WILDLIFE & PARKS

ADDENDUM NO. 1

TO: ALL BIDDERS OF RECORD

PROJECT: Somers Beach State Park Interim Improvements

FWP PROJECT #: 7216803
DATE: April 18, 2022

FROM: Randi Rognlie, Montana FWP Project Manager

Acknowledge receipt of this addendum by inserting its number and date in the Proposal Form and on the Bid Envelope. Failure to do so may subject bidder to disqualification.

This Addendum forms a part of the Contract Documents. Clarification and/or modifications area as follows:

The **Standard Form of Contract Article 2** shall be changed to read that the time of completion shall be FORTY-FIVE (45) CONSECUTIVE DAYS.

And

Bid Proposal Form:

Please replace Bid Proposal Form with the following revised form attached. The purpose is to break out the fencing as an additive alternate.

Contractor Name: _____

PROPOSAL

FWP# 7216803

Montana Fish, Wildlife & Parks
Design and Construction
PO Box 200701
1522 Ninth Avenue
Helena, Montana 59620-0701

The undersigned, having familiarized themselves with the conditions of the work and the contract documents as prepared by **A2Z Engineering, 138 East Center Street, Suite A, Kalispell, MT 59901; Phone (406) 755-7888**, agrees to furnish all labor, materials, equipment, and services necessary to complete all general construction work, as bid herein, for a project entitled **Somer's Beach State Park, Interim Improvements Project** in accordance with the Contract Documents including all Addenda. The bidder agrees to perform all the work described below at the price shown as follows:

Reminder to Contractors: All Unit Prices must be filled in on the Bid Form for a valid bid (18-2-303 MCA).

Base Bid:

Item #	Description	Estimated Quantity	Unit Measure	Unit Price	Amount
1	Vehicular and pedestrian traffic control	1	LS		
2	Construction surveying, staking and testing	1	LS		
3	Demolition, clearing and grubbing to subgrade, removal of excess excavated materials	1	LS		
4	Sub-excavation and stabilization (as directed by project engineer, remove unsuitable material below subgrade level, install imported materials)	100	CY		
5	Geotextile installation (grading, processing, sub-grade compaction and geogrid installation)	3600	SY		
6	Road base course material and installation (crushed 1.5" minus)	600	CY		
7	Road surface course material and installation (crushed 0.75" minus)	300	CY		

Contractor Name: _____

8	Entrance surfacing material and installation (asphalt)	31	Tons		
9	Final grading of stormwater ditching, check dams, and all other disturbed areas	1	LS		
10	Erosion control, re-seeding & mulching for vegetative restoration	1	LS		
11	Parking wheel-stop blocks	50	EA		
12	Transport and install FWP supplied boulders for parking & driveway delineation (30" – 40" diameter)	45	EA		
13	ADA parking signage, entrance stop sign, turn-around keep right sign	1	LS		
14	Install FWP provided 2-post kiosk and pay station	1	LS		
15	Fabricate, paint and install entrance gate.	1	LS		
16	Mobilization, bonding and submittals (no more than 4% of project bid price)	1	LS		
17	All miscellaneous items and labor not otherwise itemized in bid	1	LS		
TOTAL: \$					

BASE BID: _____

_____ AND _____ /100 DOLLARS (\$ _____)

Additive Alternate A: Wood Fencing

Description	Estimated Quantity	Unit Measure	Unit Price	Amount
Wood 2-rail fence	960	LF		

ADD ALTERNATE A: _____

_____ AND _____ /100 DOLLARS (\$ _____)

Contractor Name: _____

TOTAL BID (includes Base Bid plus all Additive Alternates):

AND _____/100 DOLLARS (\$_____).

And certifies that he is a duly and regularly licensed contractor registered with the Montana Department of Labor and Industry:

FIRM NAME: _____

TELEPHONE #: _____ FAX#: _____

BY: _____

REGISTRATION # : _____

BUSINESS ADDRESS: _____

E-MAIL ADRESS: _____