



PROJECT NAME Montana Wild Rehabilitation Ventilation Upgrades
PREBID LOCATION Montana wild
CONDUCTED BY Kristen Cull

PROJECT NUMBER 7219143
PRE-CONST. DATE Jan. 12, 2023
b.e

NAME	REPRESENTING	MAILING ADDRESS	PHONE	EMAIL
Troy Brandt	Eagle Electric		406-439-2886	troy@eagleelectricmt.com
Jake Dolezal	Sleeping Giant Mechanical		406-594-5541	jake@sleepinggiantmechanical.com
Eric Pickett	EPIC Electric		406-980-0009	eric@epicelectricmt.com



MONTANA FISH, WILDLIFE & PARKS

ADDENDUM NO. 1

TO: ALL BIDDERS OF RECORD

PROJECT: Montana Wild Rehab Ventilation Upgrades

FWP PROJECT #: 7219143

DATE: 1/17/2023

FROM: Millenium Engineering Incorporated

Acknowledge receipt of this addendum by inserting its number and date in the Proposal Form and on the Bid Envelope. Failure to do so may subject bidder to disqualification.

This Addendum forms a part of the Contract Documents. Clarification and/or modifications area as follows:


- 1) See attached Grille and Register schedule, MS-1.
- 2) MT Wild staff will remove all animals from inside the building during the project period. Provide 2 weeks of notice to owner/staff.
- 3) Bid Alternate #1: contractor shall provide labor to removal and storage of furniture, wall hangings, equipment etc from the rooms if this alternate is accepted. Storage on site where available is allowed with coordination with owner & staff.
- 4) Disconnects for HRV's are to be installed in the warm space adjacent to the HRV.
- 5) Electrical contractor shall furnish and install a dedicated 20 amp breaker for motorized dampers and control circuit. Relays, transformers and other devices shall be installed in a surface mounted box/enclosure near the electrical panel in the mechanical room.
- 6) Revised sequence of control: Motorized dampers shall operate via relay input from a current sensing relay on the supply air fan of the HRV. If supply air fan is running, the damper shall open, if the supply air fan is off the damper shall close.

GRILLE AND REGISTER SCHEDULE

<u>MARK</u>	<u>MANUFACTURER</u>	<u>MODEL</u>	<u>TYPE</u>	<u>MATERIAL</u>	<u>FINISH</u>	<u>ACCESSORIES</u>	<u>BORDER</u>	<u>FASTENING</u>	<u>THROW</u>
E-1	NAILOR	61EC	EGGCRATE EXHAUST	STEEL	WHITE	-	TYPE S	SURFACE	-
T-1	NAILOR	61EC	EGGCRATE EXHAUST	STEEL	WHITE	-	TYPE S	SURFACE	-

NOTE: PROVIDE SQUARE TO ROUND ADAPTER AS REQUIRED.

NOTE: ALL GRILLES, REGISTERS, DIFFUSERS (EXCEPT TRANSFER GRILLES) SHALL HAVE A MEANS FOR BALANCING AIRFLOW (WHETHER SHOWN ON PLANS OR NOT). UNLESS OTHERWISE NOTED GRDs INSTALLED IN LAY-IN CEILINGS SHALL HAVE MANUAL BALANCING DAMPERS IN THE DUCTWORK/TAKEOFF SERVING THE GRD. GRDs INSTALLED IN HARD SURFACES (CEILINGS/WALLS/FLOORS) SHALL HAVE OBDs FOR BALANCING AIRFLOW AS REQUIRED. ALL OBD'S INSTALLED AT THE GRD WILL BE PAINTED BLACK.



GRILLE AND REGISTER SCHEDULE

MT WILD VENTILATION ADDENDUM 1
MILLENIUM ENGINEERING INC. 01/13/2023

NO SCALE

END OF ADDENDUM NO. 1